

**ADDENDUM**

**CITY OF SOMERTON**

**ROADWAY IMPROVEMENTS –  
PARKWAY SUBDIVISION PAVEMENT PRESERVATION**

BID No. 2017-05

C.I.P. No. 2017-05

Date: January 24, 2018

From: Samuel Palacios – Public Works Director

Subject: Addendum No.1 • Replace sheet 17 (attached)

**Note: Each vendor must acknowledge receipt of this addenda and return with the bid.**

Clarification: Add the following two items as alternative bid.

Item # 501 “Remove & replace existing brick manhole 3 feet deep” per City of Yuma Standard # 5-029. Quantity 4 units

Item # 502 “Remove existing 8” sewer clay pipe and replace it with 8” SDR-35 PVC pipe. Quantity 648 LF



Samuel Palacios – Public Works Director

Company Name: \_\_\_\_\_

Contact Person: \_\_\_\_\_ Signature: \_\_\_\_\_

Address: \_\_\_\_\_

City, State, Zip: \_\_\_\_\_

Telephone Number: \_\_\_\_\_ Fax Number: \_\_\_\_\_

E-mail Address: \_\_\_\_\_

Item No.	Special Condition	Description	Quantity	Unit	Unit Cost (\$)	Total Cost (\$)
<b>Removals</b>						
1	205.001	Remove Asphalt by Milling 2" MINUS	12,213	SY		
2	400.002	Relocate Stop/Street Sign	7	EA		
3	202.003	Remove Concrete Sidewalk	2,350	SF		
5	202.005	Remove Roll Curb & Gutter	644	LF		
<b>Street Construction</b>						
21	407.021	Adjust Valve Frame & Cover to Grade	7	EA		
22	407.022	Adjust Manhole Frame & Cover to Grade	7	EA		
23	321.023	Pavement Section No. 1	12,151	SY		
26	340.026	Concrete Sidewalk	2,279	SF		
30	340.030	Curb Transition	120	LF		
32	407.032	Adjust Cleanout Frame and Cover to Grade	1	EA		
33	340.033	Sidewalk Ramp Detectable Warning Strip	5	EA		
41	407.041	Survey Monument	9	EA		
46	340.046	Roll Curb/Type "C" Curb	436	LF		
48	340.048	Driveway with Roll Curb	187	SF		
49	610.049	Relocated Fire Hydrant	1	EA		
50	610.050	6" C-900 PVC Waterline	5	LF		
51	510.051	Relocate/Replace Ex. Wall "in Kind"	216	LF		
52	340.052	Sidewalk Ramp	13	EA		
53	321.053	Pavement Section No. 2	558	SF		
		Subtotal				
<b>Miscellaneous</b>						
100	107.100	Stormwater Pollution Prevention	1	LS		
200	401.200	Traffic Control	1	LS		
300	402.300	Construction Survey and Layout	1	LS		
400	403.400	Mobilization	1	LS		

SECTION A (ITEMS 1-400): \$ \_\_\_\_\_

SECTION B CONTINGENCY (SECTION A x 10% ) \$ \_\_\_\_\_

**TOTAL CONTRACT BASE BID PROPOSAL** \$ \_\_\_\_\_  
 (SECTION A + SECTION B)

<b>Alternative bid</b>						
501		Remove & Replace Ex. Brick manhole 3 feet deep COY DTL-5-029	4	EA		
502		Remove ex. 8" sewer clay pipe and replace it with 8" SDR-35 PVC	648	LF		

**TOTAL ALTERNATIVE BID PROPOSAL** \_\_\_\_\_